

Total No. of Questions : 8]

[Total No. of Printed Pages : 3

Roll No

CE-5002-CBGS

B.E. V Semester

Examination, June 2020

Choice Based Grading System (CBGS)

Quantity Surveying and Costing

Time : Three Hours

Maximum Marks : 70

Note: i) Attempt any five questions.

ii) All questions carry equal marks.

iii) Assume suitable missing/misprint data if required.

1. a) Briefly explain the data required for preparing estimate of civil works. 7
- b) The plinth area of an apartment is 500 sqm. Determine the approximate total cost of building from the following data 7
 - i) Rate of construction = Rs. 1230/- per m³
 - ii) The height of apartment = 16.25m
 - iii) Water supply, Sanitary and Electrical installations each at 6% of building cost
 - iv) Architectural appearance @ 1% of building cost
 - v) Unforeseen item @ 2% of building cost
 - vi) P&S and contingencies @ 4% of building cost
2. a) Work out the rate analysis for 8cm thick flooring with cement concrete (1:3:6). 7
- b) What is analysis of rate? Describe the factors affecting the analysis of rate. 7

CE-5002-CBGS

PTO

[2]

3. a) Describe the center line method of estimating building with one simple example. 7
b) Explain with an example Bar bending schedule for R.C.C. 7
4. a) Discuss the provisions for overhead in estimation. 7
b) What is DPR? Explain DPR structure. 7
5. a) What do you mean by depreciation? What are the various methods of determining depreciation? Explain any one briefly. 7
b) Differentiate between: 4
i) Scrap value - Salvage value
ii) Book value - Market value
c) A person purchases a house for Rs. 10,00,000. The scrap value 10% of its construction cost. The useful life of building is 60 years. Considering the land cost Rs. 1,25,000 and rate of interest 9%. Calculate the annual installment of sinking fund. 3
6. Briefly explain following: 14
a) Specification
b) Schedule of rates
c) Rent fixation of building
d) Obsolescence
7. What is the principle of units for various items of work? State measuring units of any ten civil works. 14

[3]

8. Calculate the quantity of earthwork for a road section having following data. 14

Chainage (m)	0	30	60	90	120	150	180
G.L.(m)	80.20	80.10	79.90	79.90	79.90	79.90	79.90

Formation width 12.0m. The formation level at 90m chainage is 80.0m and the road has upward slope of 10cm in 30m. Side slope for banking 2:1 (H:V) and for cutting 1:1 (H:V).
